



NOTES!
 Electric operator complete with integral limit switch assembly, emergency hand chain and starter reverser supplied by Avon Industrial Doors Ltd.
 Client to provide a 400v, 3 phase plus neutral, 50Hz electric supply, protected by a 10amp MCB, and terminated a 4 pole 16amp isolator sited 1 metre from the opening at high level on the motor side.
 Site wiring, connection and commissioning to be undertaken by others unless previously agreed as part of the contract
 ALL electrical work to be completed by a suitably qualified electrician.

NOT TO SCALE